



выполнить ремонт в части фасада офисного здания, примыкающего к реконструируемому корпусу главного входа

Explication of premises of the 1st floor			
Number	Name	Premise category	Area
1.01	Tambour		25,36
1.02	Tambour		8,15
1.03	Guest hall		79,75
1.04	Hall		466,27
1.05	Meeting room		29,24
1.06	Hall		179,42
1.07	Security office		13,07
1.08	Post and correspondence		12,23
1.09	Security office		30,11
1.10	Changing rooms for staff		28,78
1.11	Lavatory for disabled		6,22
1.12	Technical premise	B3	5,95
1.13	Men lavatory		15,74
1.14	Women lavatory		16,28
1.15	Ventilation premise	B3	67,66
1.16	Office		36,16
1.17	Corridor		3,68
1.18	Technical premise	B3	12,87
1.19	Ventilation premise	B3	14,53
1.20	Electrical premise	B3	9,83
1.21	Corridor		48,16
Total area			1109,46

Legend	
	Reinforced concrete
	Aerated concrete blocks (утолщ.)
	Solid bricks M-100(12, 250мм)
	Facade insulated panels of reinforced concrete
	Mineral wool insulation
	Plasterboard partition (75, 100, 125, 150мм)
	Glass partition
	Border of a fire zone
	02
	04
	08
	Bb-5
	Interior doors and glass partitions

+0,000 = 129,95

Изм.	Колуч.	Лист	№ док.	Подп.	Дата
Reconstruction of the new administrative complex PJSC "Tatneft". Stage 2. Address: republic of Tatarstan, Almetyevsk, Lenina street, building 72A					
Entrance group. Reconstruction				Stage	Sheet
Plan of the 1st floor M 1:100				2	Sheets
LLC "Arcanika"					